

**UNCLASSIFIED**

**AD NUMBER**

**AD062504**

**CLASSIFICATION CHANGES**

TO: **unclassified**

FROM: **confidential**

**LIMITATION CHANGES**

TO:

**Approved for public release, distribution  
unlimited**

FROM:

**Distribution authorized to U.S. Gov't.  
agencies and their contractors;  
Administrative/Operational Use; MAY 1955.  
Other requests shall be referred to Naval  
Proving Ground, Dahlgren, VA.**

**AUTHORITY**

**USNSWC notice, 27 Aug 1981; USNSWC notice,  
27 Aug 1981**

**THIS PAGE IS UNCLASSIFIED**


AD 80504

# Armed Services Technical Information Agency

Reproduced by  
DOCUMENT SERVICE CENTER  
KNOTT BUILDING, DAYTON, 2, OHIO

Because of our limited supply, you are requested to  
RETURN THIS COPY WHEN IT HAS SERVED YOUR PURPOSE  
so that it may be made available to other requesters.  
Your cooperation will be appreciated.

NOTICE: WHEN GOVERNMENT OR OTHER DRAWINGS, SPECIFICATIONS OR OTHER DATA  
ARE USED FOR ANY PURPOSE OTHER THAN IN CONNECTION WITH A DEFINITELY RELATED  
GOVERNMENT PROCUREMENT OPERATION, THE U. S. GOVERNMENT THEREBY INCURS  
NO RESPONSIBILITY, NOR ANY OBLIGATION WHATSOEVER; AND THE FACT THAT THE  
GOVERNMENT MAY HAVE FORMULATED, FURNISHED, OR IN ANY WAY SUPPLIED THE  
SAID DRAWINGS, SPECIFICATIONS, OR OTHER DATA IS NOT TO BE REGARDED BY  
IMPLICATION OR OTHERWISE AS IN ANY MANNER CONFERRING THE HOLDER OR ANY OTHER  
PERSON BY CONVICTION, OR CONVEYING ANY RIGHTS OR PERMISSION TO MANUFACTURE,  
USE OR SELL ANY PATENTED INVENTION THAT MAY IN ANY WAY BE RELATED THERETO.



~~CONFIDENTIAL~~

NPG Report No. 1372

*FC*

DO NOT COPY  
CLASSIFIED

A STUDY OF PLASTIC LINERS FOR  
FRAGMENTATION CONTROL OF 3"/50 PROJECTILES MK 25-0



U. S. NAVAL PROVING GROUND  
DAHLGREN, VIRGINIA

~~CONFIDENTIAL~~

JUN 1 1955

Copy No. 12

Date 13 May 1955

55AA 23194

CONFIDENTIAL

U. S. Naval Proving Ground  
Dahlgren, Virginia

A Study of Plastic Liners for  
Fragmentation Control of 3"/50 Projectiles Mk 25-0  
by

J. W. Gorman  
Terminal Ballistics Department

NPG REPORT NO. 1372

Task Assignment No.  
NPG-B-2c-35-1-55

13 May 1955

APPROVED: J. F. BYRNE  
Captain, USN  
Commander, Naval Proving Ground

*E.A.Ruckner*  
E. A. RUCKNER  
Captain, USN  
Ordnance Officer  
By direction

CONFIDENTIAL

55AA 23194

CONTENTS

	<u>Page</u>
Abstract . . . . .	ii
Foreword . . . . .	iii
Introduction . . . . .	1
Description of Materials . . . . .	1
Procedure . . . . .	1
Results and Discussion . . . . .	2
Conclusions . . . . .	3
References . . . . .	3
Appendices:	
A. Drawings of Test Materials (Figures 1-3)	
B. Photographs of Recovered Fragments (Figures 4-12)	
C. Velocity Data of Fragments (Tables 1-3)	
D. Distribution	

ABSTRACT

Nine rounds of 3"/50 projectiles Mk 25-0 were loaded with Composition B and detonated in a sawdust recovery chamber for studies of mass distribution of fragments. Under study was a plastic liner furnished by Naval Ordnance Test Station, Inyokern, California designed to control the size of the fragments produced to 15.4 gram pieces approximately cubical in shape. Six of the above projectiles contained the liner, and three control projectiles did not.

The liners were considered moderately successful.

Three additional rounds were fired with liners to determine the fragment velocity characteristics. Maximum recorded velocity was 4260 ft/sec over 30°, with a median velocity of 3850 ft/sec, accurate within 5%.

FOREWORD

This is the 29th partial report on Methods of Fragmentation Control and the second partial report on Effectiveness of Plastic Liners for Fragmentation Control. This test was authorized by reference (a) and carried out under Task Assignment NPG-B-2c-35-1-55 in accordance with reference (b).

This report was reviewed by:

R. E. McCONNELL, Head, Physics Division  
Terminal Ballistics Department  
W. B. ROBERTSON, Commander, USN  
Terminal Ballistics Officer  
R. H. LYDDANE, Assistant Director of Research  
N. A. M. RIFFOLT, Director of Research

INTRODUCTION

The Naval Proving Ground has been conducting a study of various methods of controlling fragmentation and the limitations imposed upon their effectiveness by the size and shape toward which the control is aimed. This report covers a study of fluted plastic liners prepared by the Naval Ordnance Test Station and used to line projectiles before loading. The liner is designed to shape the explosive in such a way as to cut the projectile into the desired shape and size fragments.

DESCRIPTION OF MATERIALS

The liners used in this test were designed to produce cube-like fragments of approximately 15.4 grams each. The liners were made of cellulose triacetate and were shaped to fit a 3"/50 projectile Mk 25-0 (Illuminating), which is shown in Figure 1. Figure 2 is the drawing from which the liner was prepared. The projectiles were cast loaded with Composition B and fuzed with a special fuze for static detonation, Figure 3. The Mk 25 projectile was used because the approximately uniform sidewall thickness and the cylindrical cavity simplified the design and installation problems to be met in the use of liners.

All the liners were prepared at the Naval Ordnance Test Station. Some of the projectiles were loaded at the Naval Ordnance Test Station, and the remainder at the Naval Ordnance Laboratory.

PROCEDURE

Each projectile was placed in a cane fiberboard box 2' x 2' x 2', buried in sawdust in a steel chamber, and detonated. Fragments were recovered from the sawdust by means of a 1/4" mesh screen and a magnetic separator. Recovered fragments were divided into weight groups and photographed. Three lined projectiles loaded at Naval Ordnance Test Station, three loaded at Naval Ordnance Laboratory, and three unlined projectiles (to determine the "natural" mass distribution) were treated in this manner.

Three additional rounds with plastic liners, loaded at the Naval Ordnance Test Station, were placed vertically at the center of a 30' arena. This arena had 1-1/4" steel plates 15" high on its circumference in longitudinal zones 350° to 50° and 123° to 183°. Detonation of the projectiles and the fragment impacts on the plates were photographed with a 35mm Fastax camera at 2700 frames/second to obtain fragment velocity data.

#### RESULTS AND DISCUSSION

The photographs, Figures 4 through 12, show the recovered fragments and the detailed data on their numbers and weights. A summary of the weight data, given in the table below, shows the difference between the natural mass distribution and the controlled distribution for each of the two types. It is evident that the introduction of the liner has resulted in a considerable reduction of the number of fragments below about 10 grams in weight, and a corresponding increase above. The increase amounts to about 1400 grams, and its distribution is centered at about 13.5 grams for both types. The liners which were loaded at the Naval Ordnance Test Station tended to produce slightly heavier fragments, but this is of doubtful significance. The total weight of the controlled portion of the projectile is 2670 grams, and the design weight of fragments is 15.4 grams.

Detailed fragment velocity data are given in Tables 1, 2 and 3 of Appendix (C). Median velocities for the three rounds were 3800, 3850 and 3880 ft/sec, and the maximum velocity recorded was 4260 ft/sec  $\pm$  100 ft/sec.

~~CONFIDENTIAL~~

NPG REPORT NO. 1372

TOTAL WEIGHTS OF RECOVERED FRAGMENTS IN GRAMS

(Three-Round Averages)

3"/50 Mk 25-0  
Composition B Loaded

<u>Weight Group</u>	<u>Natural</u>	<u>NOTS Liner NOL Loaded</u>	<u>NOTS Liner NOTS Loaded</u>	<u>NOL Loaded- Natural</u>	<u>NOTS Loaded- Natural</u>
0	5/8	374	244	292	-130
5/8 -	1-1/4	290	136	174	-154
1-1/4 -	2-1/2	508	186	175	-322
2-1/2 -	3-1/2	311	77	86	-234
3-1/2 -	4-1/2	245	47	62	-198
4-1/2 -	5-1/2	159	35	45	-124
5-1/2 -	6-1/2	126	60	50	- 66
6-1/2 -	7-1/2	169	61	56	-108
7-1/2 -	8-1/2	163	95	99	- 68
8-1/2 -	9-1/2	107	108	96	- 11
9-1/2 -	10-1/2	96	110	117	14
10-1/2 -	11-1/2	134	236	117	102
11-1/2 -	12-1/2	111	289	274	178
12-1/2 -	13-1/2	68	441	456	373
13-1/2 -	14-1/2	97	321	442	224
14-1/2 -	15-1/2	89	190	199	101
15-1/2 -	16-1/2	32	149	111	117
16-1/2 -	17-1/2	56	85	80	29
17-1/2 -	18-1/2	36	42	66	6
18-1/2 -	19-1/2	19	38	76	19
19-1/2 +		321	562	502	241
Totals		3511	3512	3575	181

CONCLUSIONS


The liners were moderately successful in performing their intended function of controlling fragment size. Further study of this type is warranted, and possibilities of much improved performance are considered good.

REFERENCES

- (a) BUORD Conf ltr Re2c-JSM:ngh S78-1 Ser 70474  
of 3 February 1954
- (b) BUORD Conf ltr NP9-Re2c-JSM:ngh Ser 81799  
of 14 July 1954

~~CONFIDENTIAL~~

**APPENDIX A**



Best Available Copy

Figure 1

3" / 50 projectile Mk 25-O Illuminating.

NP9-67281  
CONFIDENTIAL


SIGNALMAN	
DATE	1968
INDIVIDUAL	123456
ASSISTANT	
TEST STATION	

A - 257

.000

.000

.000



NOTES

1. MATERIAL: CELLULOSE TRIACETATE  
OR CELLULOSE ACETATE.
2. LINER MUST BE FREE OF PIN HOLES.
3. RUBBER STAMP IDENTIFICATION MARK. SEE NAVORD OSTD 2.

010 ± .005

520 TYP

Electronic test set.

CENTRAL CROSS SECTIONAL  
VIEW OF LINER SHOWING  
OVERLAP JOINT  
SCALE 1

.050

1.72 ± .05

STC 1.5 2

A -

7190-0000

CHECK PRINT

CONFIDENTIAL	
RELATION OF THIS DRAWING TO OTHER DRAWINGS INVOLVED IN THIS DESIGN	REF. NO. 1
TEST STATION	TEST STATION
DEPARTMENT OF DEFENSE U.S. NAVAL ORDNANCE TEST STATION	TEST STATION


APPENDIX FOR LIMITED MATERIALS	
DO NOT SCALE THIS DRAWING	
MATERIAL:	
NEXT ASSY:	
USED ON:	
APPLICATION:	
DRAWN:	
SCALE:	
UNIT WT.:	
JOB ORDER:	
BOARD NUMBER:	
SK 553	

Figure 2

NP9-67299  
CONFIDENTIAL

Plastic liner for fragmentation control of  
3"/50 projectile Mk 25-0.

Best Available Copy



**Best Available Copy**

Figure 3

NP9-67283  
CONFIDENTIAL

Fuze for 3" /50 projectile Mk 25-O Composition B loaded with plastic liner.

## **APPENDIX B**

FRAG NO. 1856

N.P.9 NO. 66207

RD-NO. 4 NATURAL FRAGMENTATION 3/50 MK 25-1

0 - 5/8 GMS.  
PCS.  
369 GMS.

5/8 - 1 1/8 GMS.  
342 PCS.  
298 GMS.

1 1/8 - 2 1/8 GMS.  
284 PCS.  
498 GMS.

2 1/8 - 5 GMS.  
174 PCS.  
588 GMS.

5 - 10 GMS.  
105 PCS.  
738 GMS.

10 - 20 GMS.  
50 PCS.  
664 GMS.

20 - 40 GMS.  
10 PCS.  
260 GMS.

40 - 80 GMS.  
2 PCS.  
118 GMS.

FUZE-FRAGS.  
93 PCS.  
427 GMS.

SCALE 1"

Figure 4

NP9-66207  
CONFIDENTIAL

Recovered fragments from unlined control 3" /50  
projectile Mk 25-0.

FRAG NO. 1857

RD-NO. 5 NATURAL FRAGMENTATION 3/50 MK.25-1

N.P.9 NO. 66208

0 - 5/8 GMS.  
PCS.  
391 GMS.

5/8 - 1 GMS.  
325 PCS.  
287 GMS.

1 - 2 GMS.  
317 PCS.  
556 GMS.


2 - 5 GMS.  
179 PCS.  
600 GMS.

5 - 10 GMS.  
94 PCS.  
660 GMS.

10 - 20 GMS.  
55 PCS.  
726 GMS.

20 - 40 GMS.  
3 PCS.  
74 GMS.  
40 - 80 GMS.  
1 PCS.  
41 GMS.  
80 - 160 GMS.  
1 PCS.  
134 GMS.

FUZE-FRAGS.  
114 PCS.  
435 GMS.



SCALE 1

Figure 5

NP9-66208  
CONFIDENTIAL

Recovered fragments from unlined control 3"/50  
projectile Mk 25-0.

FRAG NO. 1859

0 - 5/8 GMS.  
362 PCS.  
GMS.

RD - NO. 6 NATURAL FRAGMENTATION 3/50 MK 25-1

N.P.9 NO. 66254

5/8 - 1/2 GMS.  
326 PCS.  
285 GMS.

1 1/2 - 2 GMS.  
271 PCS.  
470 GMS.

2 1/2 - 5 GMS.  
201 PCS.  
712 GMS.

5 - 10 GMS.  
97 PCS.  
684 GMS.

10 - 20 GMS.  
58 PCS.  
766 GMS.

20 - 40 GMS.  
7 PCS.

157 GMS.

80 - 160 GMS.

101 PCS.

FUZE-FRAGS.

121 PCS.  
438 GMS.

SCALE 1"

Figure 6

NP9-66254  
CONFIDENTIAL

Recovered fragments from unlined control 3"/50  
projectile Mk 25-0.

FRAG NO. 1848

PLASTIC LINER FOR FRAGMENTATION CONTROL 3/50 MK 25-1 RD. NO. 1

N.P.9 NO. 65944

0 - 5/8	GMS.
	PCS.
2 4 5 . 1	GMS.
5 1/2 - 1 1/2	GMS.
1 3 8	PCS.
1 2 0 . 8	GMS.
1 - 2 .	GMS.
9 5	PCS.
1 6 3 . 1	GMS.
2 1/2 - 3 1/2	GMS.
2 4	PCS.
7 0 . 0	GMS.
3 - 4 .	GMS.
1 1	PCS.
4 2 . 2	GMS.
4 - 5	GMS.
8	PCS.
3 9 . 4	GMS.
5 - 6 .	GMS.
1 1	PCS.
6 6 . 1	GMS.
6 - 7	GMS.
9	PCS.
6 2 . 3	GMS.
7 - 8	GMS.
1 0	PCS.
7 9 . 2	GMS.
8 - 9	GMS.
1 3	PCS.
1 1 6 . 2	GMS.
9 - 10	GMS.
8	PCS.
8 0 . 1	GMS.
1 0 - 1 1	GMS.
2 7	PCS.
2 9 8 . 4	GMS.
1 1 - 1 2	GMS.
2 5	PCS.
3 0 1 . 7	GMS.
1 2 - 1 3	GMS.
3 0	PCS.
3 8 9 . 9	GMS.
1 3 - 1 4	GMS.
2 2	PCS.
3 0 8 . 9	GMS.
1 4 - 1 5	GMS.
1 4	PCS.
2 0 9 . 3	GMS.
1 5 - 2 0	GMS.
1 9	PCS.
3 2 3 . 2	GMS.
2 0 +	GMS.
1 4	PCS.
5 8 4 . 0	GMS.
FUZE-FRAGS.	
6 6	PCS.
4 4 0 . 2	GMS.



Figure 7

NP9-65944  
CONFIDENTIAL

Recovered fragments from 3"/50 projectile Mk 25  
with Naval Ordnance Test Station liner loaded  
at Naval Ordnance Laboratory.

FRAG NO. 1849

N.P.9 NO. 65993

PLASTIC LINER FOR FRAGMENTATION CONTROL 3/50 MK 25-1 RD - NO. 2

0 - 5	GMS.
	PCS.
258.2	GMS.
5/8 - 1	GMS.
179	PCS.
149.8	GMS.
1 - 2	GMS.
125	PCS.
218.6	GMS.
212 - 3 1/2	GMS.
30	PCS.
84.8	GMS.
3 - 4	GMS.
14	PCS.
53.7	GMS.
4 - 5	GMS.
6	PCS.
29.6	GMS.
52 - 6	GMS.
12	PCS.
72.1	GMS.
62 - 7	GMS.
13	PCS.
919	GMS.
72 - 8	GMS.
9	PCS.
713	GMS.
8 - 9	GMS.
15	PCS.
135.7	GMS.
9 - 10	GMS.
16	PCS.
159.6	GMS.
10 - 11	GMS.
17	PCS.
189.3	GMS.
11 - 12	GMS.
26	PCS.
310.6	GMS.
12 - 13	GMS.
42	PCS.
542.9	GMS.
13 - 14	GMS.
14	PCS.
194.3	GMS.
14 - 15	GMS.
11	PCS.
165.1	GMS.
15 - 20	GMS.
17	PCS.
286.8	GMS.
20 +	GMS.
10	PCS.
491.1	GMS.
FUZE-FRAGS.	
108	PCS.
454.8	GMS.

SCALE 1

Figure 8

NP9-65993  
CONFIDENTIAL

Recovered fragments from 3"/50 projectile Mk 25  
with Naval Ordnance Test Station liner loaded  
at Naval Ordnance Laboratory.

FRAG NO. 1851

PLASTIC LINER FOR FRAGMENTATION CONTROL 3/50 MK 25-1 RD - NO. 3

N.P.9 NO. 65996

0 - 5 GMS.

PCS.

227.5 GMS.

5/8 - 1 1/4 GMS.

PCS.

16.9 GMS.

PCS.

1 1/2 - 2 GMS.

PCS.

17.6.6 GMS.

PCS.

2 1/2 - 3 1/4 GMS.

PCS.

2.6 GMS.

PCS.

7.5.2 GMS.

PCS.

3 1/2 - 4 1/2 GMS.

PCS.

4.6.3 GMS.

PCS.

4 1/2 - 5 GMS.

PCS.

3.5.0 GMS.

PCS.

5 1/2 - 6 GMS.

PCS.

7 GMS.

PCS.

4 1/2 GMS.

PCS.

6 1/2 - 7 GMS.

PCS.

4 GMS.

PCS.

27.9 GMS.

PCS.

7 1/2 - 8 GMS.

PCS.

17 GMS.

PCS.

134.0 GMS.

PCS.

8 - 9 GMS.

PCS.

70.8 GMS.

PCS.

9 - 10 GMS.

PCS.

91.4 GMS.

PCS.

10 - 11.2 GMS.

PCS.

20 GMS.

PCS.

219.3 GMS.

PCS.

11 - 12 GMS.

PCS.

255.6 GMS.

PCS.

12 - 13 GMS.

PCS.

30 GMS.

PCS.

391.6 GMS.

PCS.

13 - 14 GMS.

PCS.

460.0 GMS.

PCS.

14 - 15 GMS.

PCS.

194.7 GMS.

PCS.

15 - 20 GMS.

PCS.

22 GMS.

PCS.

370.1 GMS.

PCS.

20 + GMS.

PCS.

571.7 GMS.

PCS.

FUZE-FRAGS.

73 PCS.

451.8 GMS.

SCALE 1

Figure 9

NP9-65996  
CONFIDENTIAL

Recovered fragments from 3"/50 projectile Mk 25  
with Naval Ordnance Test Station liner loaded  
at Naval Ordnance Laboratory.

FRAG NO. 1876

PLASTIC LINER FOR FRAGMENTATION CONTROL 3/50 MK 25-1 RD. NO. N.O.T.S - 1 N.P.9 NO. 66904

0 - 5% GMS.

PCS.

285.8 GMS.

58 - 1/4 GMS.

217 PCS.

183.8 GMS.

14 - 2 1/2 GMS.

95 PCS.

161.0 GMS.

2 1/2 - 3 1/2 GMS.

34 PCS.

98.5 GMS.

3 1/2 - 4 1/2 GMS.

22 PCS.

83.4 GMS.

4 1/2 - 5 GMS.

11 PCS.

55.5 GMS.

5 1/2 - 6 1/2 GMS.

7 PCS.

41.7 GMS.

6 1/2 - 7 GMS.

8 PCS.

55.3 GMS.

7 1/2 - 8 GMS.

13 PCS.

103.2 GMS.

8 - 9 GMS.

11 PCS.

97.4 GMS.

9 - 10 GMS.

14 PCS.

140.6 GMS.

10 - 11 1/2 GMS.

14 PCS.

154.4 GMS.

11 - 12 GMS.

18 PCS.

217.8 GMS.

12 - 13 GMS.

33 PCS.

431.3 GMS.

13 - 14 GMS.

32 PCS.

447.8 GMS.

14 - 15 GMS.

13 PCS.

193.4 GMS.

15 - 20 GMS.

21 PCS.

359.6 GMS.

20 + GMS.

11 PCS.

467.5 GMS.

FUZE-FRAGS.

166 PCS.

450.5 GMS.

SCALE

Figure 10

NP9-66904  
CONFIDENTIAL

Recovered fragments from 3"/50 projectile Mk 25 with Naval Ordnance Test Station liner loaded at Naval Ordnance Test Station.

FRAG NO. 1877  
0 - 5/8 GMS. PLASTIC LINER FOR FRAGMENTATION CONTROL 3/50 MK 25 - 1 RD NO. N.P.9 NO. 66935  
299.5 PCS. N.O.T.S - 2

5/8 - 1/4 GMS.  
185 PCS.  
156.4 GMS.  
14-2 1/2 GMS.  
103 PCS.  
178.0 GMS.  
23-3 GMS.  
26 PCS.  
74.9 GMS.  
32-4 GMS.  
16 PCS.  
64.6 GMS.  
42-5 1/2 GMS.  
5 PCS.  
24.2 GMS.  
52-6 GMS.  
8 PCS.  
48.4 GMS.  
62-7 GMS.  
11 PCS.  
78.5 GMS.  
72-8 GMS.  
10 PCS.  
80.7 GMS.  
8 PCS.  
72.5 GMS.  
9-10 PCS.  
9 GMS.  
88.3 GMS.  
10-11 GMS.  
9 PCS.  
98.6 GMS.  
11-12 GMS.  
22 PCS.  
265.5 GMS.  
12-13 GMS.  
42 PCS.  
547.8 GMS.  
13-14 GMS.  
25 PCS.  
348.6 GMS.  
14-15 GMS.  
19 PCS.  
283.6 GMS.  
15-20 GMS.  
16 PCS.  
281.5 GMS.  
20+ GMS.  
15 PCS.  
611.6 GMS.

FUZE-FRAGS.  
202 PCS.  
471.9 GMS.

SCALE

Figure 11

NP9-66935  
CONFIDENTIAL

Recovered fragments from 3"/50 projectile Mk 25  
with Naval Ordnance Test Station liner loaded  
at Naval Ordnance Test Station.

Frag No. 1878 PLASTIC LINER FOR FRAGMENTATION CONTROL 3/50 MK 2.5 - 1 RD NO. N.O.T.S - 3  
NP9 NO. 67037

0 - 5/8 GMS.  
GMS.  
GMS.  
317.4 GMS.

58 - 1/4 GMS.  
222 PCS.  
GMS.  
181.4 GMS.  
1 1/4 - 2 1/2 GMS.  
110 PCS.  
GMS.  
187.1 GMS.  
2 - 3 GMS.  
29 PCS.  
85.0 GMS.  
3 - 4 GMS.  
10 PCS.  
39.5 GMS.  
4 - 5 GMS.  
54.8 GMS.  
5 - 6 GMS.  
10 PCS.  
60.7 GMS.  
6 - 7 GMS.  
5 PCS.  
35.6 GMS.  
7 - 8 GMS.  
14 PCS.  
113.1 GMS.  
8 - 9 GMS.  
13 PCS.  
116.7 GMS.  
9 - 10 GMS.  
12 PCS.  
120.9 GMS.  
10 - 11 GMS.  
9 PCS.  
99.0 GMS.  
11 - 12 GMS.  
28 PCS.  
338.8 GMS.  
12 - 13 GMS.  
30 PCS.  
389.2 GMS.  
13 - 14 GMS.  
38 PCS.  
528.5 GMS.  
14 - 15 GMS.  
8 PCS.  
119.2 GMS.  
15 - 20 GMS.  
23 PCS.  
398.1 GMS.  
20 + GMS.  
11 PCS.  
385.8 GMS.

FUZE-FRAGS.  
183 PCS.  
460.9 GMS.

Figure 12

NP9-67037  
CONFIDENTIAL

Recovered fragments from 3"/50 projectile Mk 25  
with Naval Ordnance Test Station liner loaded  
at Naval Ordnance Test Station.

## **APPENDIX C**

CONFIDENTIAL

NPG REPORT NO. 1372

TABLE 1

FRAGMENT VELOCITY DATA

Date: 2 December 1954  
30 Ft. Radius Arena  
35mm Fastax Camera  
Rd. No. 1 3"/50 Mk 25

2700 Frames per second  
Filler Composition B

<u>Frame in Which Hit Occurred</u>	<u>No. Fragments</u>	<u>Velocity (f/s)</u>
20	18	4050
21	9	3860
22	12	3680
23	6	3520
24	4	3380
25	5	3240
26	2	3120
Median		3850
Average		3730

CONFIDENTIAL

CONFIDENTIAL

NPG REPORT NO. 1372

TABLE 2

FRAGMENT VELOCITY DATA

Date: 2 December 1954                            2700 Frames per second  
30 Ft. Radius Arena                                Filler Composition B  
35mm Fastax Camera  
Rd. No. 2 3<sup>1</sup>/<sub>2</sub>/50 Mk 25

<u>Frame in Which Hit Occurred</u>	<u>No. Fragments</u>	<u>Velocity (f/s)</u>
20	14	4050
21	13	3860
22	8	3680
23	6	3520
24	5	3380
25	9	3240
26	1	3120
Median		3800
Average		3690

CONFIDENTIAL

CONFIDENTIAL

NPG REPORT NO. 1372

TABLE 3

FRAGMENT VELOCITY DATA

Date: 2 December 1954  
30 Ft. Radius Arena  
35mm Fastax Camera  
Rd. No. 3 3"/50 Mk 25

2700 Frames per second  
Filler Composition B

<u>Frame in Which Hit Occurred</u>	<u>No. Fragments</u>	<u>Velocity (f/s)</u>
19	7	4260
20	15	4050
21	11	3860
22	8	3680
23	3	3520
24	4	3380
25	6	3240
27	4	3000
28	1	2890
Median		3880
Average		3740

CONFIDENTIAL

**APPENDIX D**

**CONFIDENTIAL**

**NPG REPORT NO. 1372**

**DISTRIBUTION**

**Bureau of Ordnance:**

Ad3	1
Re2	2
Re3	1
Re2c	5

Armed Services Technical Information Agency  
Document Service Center  
Knott Building  
Dayton 2, Ohio

5

Commanding General  
Aberdeen Proving Ground  
Aberdeen, Maryland  
Attn: Technical Information Section  
Development and Proof Services

2

Commander, Operational Development Force  
U. S. Atlantic Fleet, U. S. Naval Base  
Norfolk 11, Virginia

1

Naval Ordnance Laboratory

1

Naval Ordnance Laboratory  
Attn: Explosives Research Department  
Attn: Missiles Division

2

1

Picatinny Arsenal, Dover, N. J.  
Attn: Technical Division

1

Reports Office  
APL/JHU, Silver Spring, Maryland

1

Bureau of Ordnance Technical Liaison Office  
Bell Telephone Laboratories  
Whippany, New Jersey

1

USNOTS, Inyokern, China Lake, California

2

**CONFIDENTIAL**

1

**CONFIDENTIAL**

**NPG REPORT NO. 1372**

-----

**DISTRIBUTION (Continued)**

Institute of Cooperative Research  
JHU/1315 St. Paul St.  
Via: (District Chief, Phila. Ord District  
1500 Chestnut St., Phila. 2, Pa.  
Attn: Mr. Edward R. C. Niles) 1

Commanding Officer  
Frankford Arsenal  
Philadelphia, Pennsylvania 1

Local:

OT 1  
OTX 1  
File 1

**CONFIDENTIAL**

**2**

<p><b>NPG 1372</b></p> <p>Naval Proving Ground, Dahlgren, Virginia</p> <p>A STUDY OF PLASTIC LINERS FOR FRAGMENTATION CONTROL OF 3" / 50 PROJECTILES MK 25-O, by J. W. German. 13 May 1955. 3p., tables. append A-D. (NPG Report No. 1372. Task assignment NPG-B-2c-35-1-55).</p> <p><b>CONFIDENTIAL</b></p> <p>Nine rounds of 3" / 50 projectiles Mk 25-O were loaded with Composition B and detonated in a quadrant recovery chamber for studies of mass distribution of fragments.</p> <p>Under study was a plastic liner furnished by Naval Ordnance Test Station, Inyokern, California designed to control the size of fragments produced to 15.4 gram pieces approximately cubical in shape. Six of the above projectiles contained the liner, and three control projectiles did not.</p> <p>The liners were considered moderately successful. Three additional rounds were fired with liners to determine the fragment velocity characteristics.</p>	<p>1. Projectiles - 3" / 50 - Mark 25. Mod 0 - Fragmentation 2. Projectile fragments - Velocity</p> <p>1. Gorman, J. W.</p> <p>2. Projectile fragments - Velocity</p> <p>1. Gorman, J. W.</p> <p><b>CONFIDENTIAL</b></p> <p>Nine rounds of 3" / 50 projectiles Mk 25-O were loaded with Composition B and detonated in a quadrant recovery chamber for studies of mass distribution of fragments.</p> <p>Under study was a plastic liner furnished by Naval Ordnance Test Station, Inyokern, California designed to control the size of fragments produced to 15.4 gram pieces approximately cubical in shape. Six of the above projectiles contained the liner, and three control projectiles did not.</p> <p>The liners were considered moderately successful. Three additional rounds were fired with liners to determine the fragment velocity characteristics.</p>
<p><b>NPG 1372</b></p> <p>Naval Proving Ground, Dahlgren, Virginia</p> <p>A STUDY OF PLASTIC LINERS FOR FRAGMENTATION CONTROL OF 3" / 50 PROJECTILES MK 25-O, by J. W. German. 13 May 1955. 3p., tables. append A-D. (NPG Report No. 1372. Task assignment NPG-B-2c-35-1-55).</p> <p><b>CONFIDENTIAL</b></p> <p>Nine rounds of 3" / 50 projectiles Mk 25-O were loaded with Composition B and detonated in a quadrant recovery chamber for studies of mass distribution of fragments.</p> <p>Under study was a plastic liner furnished by Naval Ordnance Test Station, Inyokern, California designed to control the size of fragments produced to 15.4 gram pieces approximately cubical in shape. Six of the above projectiles contained the liner, and three control projectiles did not.</p> <p>The liners were considered moderately successful. Three additional rounds were fired with liners to determine the fragment velocity characteristics.</p>	<p>1. Projectiles - 3" / 50 - Mark 25. Mod 0 - Fragmentation 2. Projectile fragments - Velocity</p> <p>1. Gorman, J. W.</p> <p>2. Projectile fragments - Velocity</p> <p>1. Gorman, J. W.</p> <p><b>CONFIDENTIAL</b></p> <p>Nine rounds of 3" / 50 projectiles Mk 25-O were loaded with Composition B and detonated in a quadrant recovery chamber for studies of mass distribution of fragments.</p> <p>Under study was a plastic liner furnished by Naval Ordnance Test Station, Inyokern, California designed to control the size of fragments produced to 15.4 gram pieces approximately cubical in shape. Six of the above projectiles contained the liner, and three control projectiles did not.</p> <p>The liners were considered moderately successful. Three additional rounds were fired with liners to determine the fragment velocity characteristics.</p>